

Notes:

2- Small roots (1/4" or less) that grow around, up, or down the root ball periphery are considered a normal condition in container production and are acceptable however they should be eliminated at the time of planting. Roots on the periperhy can be removed at the time of planting. (See root ball shaving container detail).

3- Settle soil around root ball of each groundcover prior to mulching.



GROUNDCOVER

